

File.

MP00053

**Knight Piésold Ltd.**  
CONSULTING ENGINEERS

Suite 1400  
750 West Pender Street  
Vancouver, British Columbia  
Canada V6C 2T8  
Telephone (604) 685-0543  
Telefax (604) 685-0147  
CIS: 72360,477 1625.01  
YOUR REFERENCE  
OUR REFERENCE 5/1046  
NUMBER May 5, 1995

Mr. Malcolm Swallow  
Imperial Metals Corporation  
Suite 700 - 815 West Hastings Street  
Vancouver, B.C. V6C 1B4

Dear Malcolm,

Re: Mt. Polley Project  
Surface Water Control

A preliminary evaluation of the mine site Surface Water Control Program has been completed. All ponds, ditches, etc. have been sized to allow for complete containment of runoff from the 10 year 24 hour storm event. The mill site runoff collection system will allow for containment of larger storm events, as discussed below.

The layout of the overall drainage plan for the mine site is presented on Drawing No. 1625.230. The mill site area is isolated on Drawing No. 1625.231 and Sections and Details are shown on Drawing No. 1625.232.

Control of surface water runoff at the mill site will initially be accomplished by excavating preconstruction diversion ditches around the perimeter of the mill area, thereby greatly reducing the direct catchment and subsequent runoff volumes. After the preconstruction ditches are completed, a confining berm will be constructed from surficial materials excavated during mill site preparation. The berm will contain salvageable soils (Bf, Bm, Bt and C horizons), as well as rocky till which is expected at higher elevations. The different soil types will be separated in the berm as shown on the sections. The berm terminates at the main access road and runoff is channelled across the road and into the Mill Site Sump by means of a ditch and cattle guard.

The mill site area will be graded to the south east corner, where the Mill Site Sump is located. This sump has a live storage of approximately 6,000 cubic metres, which is 1.5 times the 1 in 10 year 24 hour runoff for the mill site catchment. Runoff will then be passed to the tailings storage facility through an outlet pipe to a drop box on



Association  
of Consulting  
Engineers  
of Canada

Association  
des Ingénieurs-  
Consultants  
du Canada

GRIT 2195

**Knight Piesold Ltd.**  
CONSULTING ENGINEERS

the tailings line, which has the ability to continuously remove in excess of 0.1 cubic metres per second of storm runoff together with the tailings flow. This storm runoff represents 8,300 cubic metres per day, which is equivalent to a storm event at the mill site in excess of the 1 in 100 year 24 hour rainfall. Therefore, the mill site runoff control system is capable of routing all runoff for up to the 1 in 100 year 24 hour event through to the tailings storage facility during normal mill operations. For larger storm events, additional runoff volumes can be accommodated by stopping the milling process and thus removing tailings slurry transfer. There is also the provision that the runoff to the Mill Site Sump can be pumped directly back to the process.

The surface water runoff for the overall mine site will be controlled by conscientious waste dump development and construction of the Pit Dewatering Sump and the South Sediment Pond as well as a series of diversion ditches. The waste dumps will be sloped so that runoff is directed toward the Pit Dewatering Sump, where it can return via gravity to the mill process. If the Pit Dewatering Sump overflows, the runoff will be directed so that it will flow into the open pit.

Additional control measures for the overall mine site include the excavation of diversion ditches along the bottom of the waste dumps. Runoff will be directed to the South Sediment Pond which has been sized according to the 10 year 24 hour criteria as for the other ponds. The runoff will be directed to the tailings storage facility through a low level outlet to a drop box on the tailings line.

79

The long term plan for control of surface water at the north and west sides of the mine site are conceptual only at this time. The details are currently being developed.

Yours very truly,  
KNIGHT PIESOLD LTD.




K.J. Brouwer, P.Eng.  
Director

KDE/ke



Association  
of Consulting  
Engineers  
of Canada

Association  
des Ingénieurs  
Conseillers  
du Canada




**KNIGHT PIESOLD**  
CONSULTING ENGINEERS - V.A.

DESIGNED
DRAWN
CHECKED
APPROVED

DATE **MAY 5, 1995**

**NOTE**  
 1. North and West Sediment Control facilities are conceptual only.  
 2. Pit Dewatering Sump to be enlarged as necessary for Waste Dump expansion.


REV.	DATE	DESCRIPTION	APPROVED	REV.	DATE	DESCRIPTION	APPROVED
				<b>A</b>	<b>MAY 5/95</b>	<b>ISSUED FOR COMMENTS</b>	
REVISIONS				REVISIONS			




**NOTE**  
 1. North and West Sediment Control facilities are conceptual only.  
 2. Pit Dewatering Sump to be enlarged as necessary for Waste Dump expansion

<b>KNIGHT PIESOLD LIMITED</b> CONSULTING ENGINEERS - VANCOUVER, B.C.		<b>IMPERIAL METALS CORPORATION</b>	
		<b>MT. POLLEY PROJECT</b>	
		<b>DRAINAGE PLAN</b> <b>MINE SITE</b>	
DESIGNED: KOE/MM DRAWN: RDT/VT CHECKED: APPROVED:			
DATE <b>MAY 5, 1995</b>	SCALE AS SHOWN	DRG. NO. <b>1625.230</b>	REV. <b>A</b>

3/95	ISSUED FOR COMMENTS	
DATE	DESCRIPTION	APPROVED
REVISIONS		



DATE	DESCRIPTION	REV.	DATE	DESCRIPTION	APPROVED	REV.
	REFERENCE DRAWINGS			REVISIONS		




**KNIGHT PIESOLD L**  
CONSULTING ENGINEERS - VANC

DESIGNED
DRAWN
CHECKED
APPROVED



REV.	DATE	DESCRIPTION	APPROVED
A	MAY 5/95	ISSUED FOR COMMENTS	

DATE **MAY 5, 1995**







REV. NO.	DESCRIPTION	REV.	DATE	DESCRIPTION	APPROVED	A	MA
REFERENCE DRAWINGS				REVISIONS			





SECTION 1625.231  
MILL SITE BERM SECTION  
Scale A

1  
230  
TROL POND



SECTION 1625.231  
TYPICAL DITCH SECTION  
Scale A

2  
231  
WP



DROP BOX - CONCEPTUAL  
NTS

installed in trench required

3  
230  
SUMP


CRITERIA
5 x 10yr 24 hour precipitation and at start-up of operations
5 x 10yr 24 hour precipitation and at start-up of operations
5 x 10yr 24 hour precipitation and

total volume  
waste dump expansion.  
open pit inflows.


**KNIGHT CONSULTING E**

DATE: MAY

REV.	DATE	DESCRIPTION	APPROVED	REV.	DATE	DESCRIPTION	APPROVED
A	MAY 5/95	ISSUED FOR COMMENTS					




**SECTION 4**  
**ALL SITE BERM SECTION**  
Scale A



Ditch dimensions to follow


**SECTION 5**  
**TYPICAL DITCH SECTION**  
Scale A






**P BOX - CONCEPTUAL**  
NTS

**NOTES**

1. Water level controlled by added/removing rings in decant.
2. Sediment control berm to be constructed using suitable glacial till materials from local excavations.
3. Mill site berm to be constructed with material excavated during site preparation. All soil types can be placed in the berm, but they must be separated.
4. Mill site berm to be constructed in max. 0.5 m fills, with compaction provided by trackwalking the surface prior to placement of the next fill.
5. Silt fence and hay bales provided for sediment control.
6. Rockfill to comprise clean coarse gravel and cobbles.
7. All pond excavations and fill sections to be completed in low permeability glacial till materials.



KNIGHT PIESOLD LIMITED CONSULTING ENGINEERS - VANCOUVER, B.C.		IMPERIAL METALS CORPORATION MT. POLLEY PROJECT	
DESIGNER: KCE/MM DRAWN: RDT CHECKED: APPROVED:		DRAINAGE PLAN SECTIONS AND DETAILS	
REVISIONS 795 ISSUED FOR COMMENTS			
DATE: MAY 5 1995		SCALE: AS SHOWN	GRC. NO. 1625.232
		REV. A	



Reacto pump  
Sedim. dischr.  
Sump  
Removeable access hole  
2 m min.  
Low velocity tailings infler

POND	STORAGE VOLUMES (m <sup>3</sup> )		CRITERIA
	Live Storage	Dead Storage	
South Sediment Pond	15,000	3,250	1.5 x 10yr 24 hour precipitation event at start-up of operations
Pit Dewatering Sump	- Initial	12,800	1.5 x 10yr 24 hour precipitation event at start-up of operations
	- Final	24,400	
Mill Site Sump	6,000	1,000	1.5 x 10yr 24 hour precipitation event

**NOTE**

1. Initial Pit Dewatering Sump approx. 50% of final volume. Sump size to be increased in conjunction with waste dump expansion.
2. Final Pit Dewatering Sump includes 10% of Open Pit inflows.

DESC. NO.	DESCRIPTION	REV.	DATE	DESCRIPTION	APPROVED	A	AA
	REFERENCE DRAWINGS			REVISIONS			